



| FOR BETWEEN JAMB |    | FOR BETWEEN JAMB |       | FOR BETWEEN JAMB |        |
|------------------|----|------------------|-------|------------------|--------|
| GUIDE TYPE       | A" | B"               | C"    | D"               | F"     |
| Z                | 3  | 4 1/4            | 5 1/2 | 5/8              | 3      |
| E                |    | 1 15/16          | 3 1/2 | 5/8              | 3 3/16 |
| SQ3              |    |                  | 6     | 5/8              | 3      |
| SQ4              |    |                  | 7     | 7/8              | 4      |

**MINIMUM SIDE ROOM CLEARANCES REQUIREMENTS:**

| ELECTRIC OPERATOR |    |
|-------------------|----|
| DRIVE C           | 6" |
| TENSION           | 6" |

**GENERAL NOTES**

STANDARD:  
CURTAIN: TO BE CLEAR ANODIZED HOLLOW TUBES OVER COLD ROLLED 1/4" STEEL RODS. MILL FINISH LINKS.

BOTTOM BAR: CLEAR ANODIZED ALUMINUM.

GUIDES: CLEAR ANODIZED ALUMINUM WITH POLYETHYLENE INSERT.

NON ALUMINUM SURFACES: TO BE SHOP COATED WITH RUST INHIBITING PRIMER.

OPERATION: LIFTMASTER GH OPERATOR. (RIGHT HAND SHOWN)



| TOP MOTOR CLEARANCE |     |     |     |
|---------------------|-----|-----|-----|
| HP                  | 14" | 16" | 22" |
| Z                   | 9"  | 8"  | 5"  |

500-GH

12-02-02

| QTY. | OPENING SIZE |            | OPERATION | RH<br>LH | CLEARANCES |     | OPTION | PROJECT:   |             |              |       |            |     |         |  |  |
|------|--------------|------------|-----------|----------|------------|-----|--------|------------|-------------|--------------|-------|------------|-----|---------|--|--|
|      | WIDTH "W"    | HEIGHT "H" |           |          | "X"        | "Y" |        | ARCHITECT: | CONTRACTOR: | DISTRIBUTOR: | DATE: | SHEET: OF: | BY: | REF. #. |  |  |
|      |              |            |           |          |            |     |        |            |             |              |       |            |     |         |  |  |
|      |              |            |           |          |            |     |        |            |             |              |       |            |     |         |  |  |
|      |              |            |           |          |            |     |        |            |             |              |       |            |     |         |  |  |
|      |              |            |           |          |            |     |        |            |             |              |       |            |     |         |  |  |



**MODEL 500 - GH MOTOR OPERATED GRILLE**

NOTE: Porvene Doors is not responsible for improper installation procedures, structural backing, and field inspections of the project itself.

APPROVAL SIGNATURE: \_\_\_\_\_ DATE SIGNED: \_\_\_\_\_